Egyptian Electricity Holding Company Laboratories, research and testing sector Extra High Voltage Research Center



الشركة القابضة لكهرباء مصر قطاع المعامل والبحوث والاختبارات مركز أبحاث الجهد الفائق

الموضدوع: اختبار كشاف إضاءة شوارع ليد قدرة (١٠٠) وات طراز: (TU) - انتاج شركة طيبة للصناعات المتطورة .

السيد المهندس / مدير إدارة الاضاءة شركة طيبة للصناعات المتطورة

تحية طيبة وبعد ،،،،

بالاشارة إلى كتاب سيادتكم واستلام العينة بتاريخ ٢٠٢/٤/٢١ م، بخصوص الموضوع عاليه.

نتشرف بالاحاطه بأنه تم إجراء الاختبارات المطلوبه وتم إعداد التقرير الفنى رقم (٢٠٢/٢٥٤) المتضمن نتائج الاختبارات علما بان تكاليف إجراء الاختبارات هى مبلغ وقدره (٩٣٨١) جنيه (فقط وقدره تسعة الاف وثلاثمائة وواحد وثمانون جنيها مصربا لاغير) شاملة ١٤ % قيمة ضرببة القيمة المضافة

وقد تم سداد المبلغ المشار اليه بعاليه وتم استلام التقرير الفني المكون من (٥)صفحة

وتفضلوا بقبول فائق الاحترام والتقدير ،،،،

مدير عام الأدارة العامة للمعايرة والحودة الشاملة

رئيس قسم الشئون المالية بالمركز

محاسب/ ربيع محد عبدالعزيز

رئيس قطاع

المعامل والبحوث والاختبارات

"د. مهندس/ سلوی علي أحمد"

شریف ۲۰۲۲/٦/۱۵



مقر المركز: طريق القاهرة – الإسكندرية الصحراوي – الكيلو ٢٧ – ت: ٣٥٣٩،٧٢٨ – فاكس: ٣٥٣٩،٧٣١ عنوان المراسلات: Email: eng salwa 2010@hotmail.com



الشركة القابضة لكهرباء مصر قطاع المعامل والبحوث والاختبارات مركز أبحاث الجهد الفائق الكبو٢٧ طربق الفامرة //إسكندرية الصعراوي رقم التقرير: (٢٥٤ /٣٠٣)

TEST REPORT

REPORT No. (254/2022)

CLIENT: TEBA for Development Industries.

Plot No.1 –Industrial Zone(7A) – 10^{th} of Ramadan- Egypt.

Report Date: 15/6/2022.

■ Place:

- EXTRA HIGH VOLTAGE RESEARCH CENTER LABORATORIES
- Internal Code: TO AC 22 04 26 06.

"Requirements:

- Test of LED street lighting luminaires (100) watt according to IEC standard.

Standard Specification:

- IEC (60598 –1)/(2008) : Luminaires Part 1: General requirements and tests.
- IEC (62722-2-1)/(2011): Luminaire performance Part 2-1: Particular requirements for LED luminaires.
- IEC (62717)/(2015) : LED Modules for general lighting-Performance requirements.
- IEC (61000-3-2)/(2018): Electromagnetic compatibility (EMC) Part 3-2: Limits -Limits for harmonic current emissions(equipment input current ≤ 16 A per phase).

■ Description of Specimen:

- LED street lighting luminaire (100) watt - Type: (TU) - Rated Input power: (100) Watt - Manufactured by TEBA for Development Industries - Made in Egypt.

Description of Testing Equipment:

- 1. Measure Device: Everfine GO-2000A v1.
- 2. Power analyzer, Model: (HIOKI-3196) Certificate No.: (218/23/2020).
- 3. Two voltage transformers Type: (UZGT10) Serial No.: (929130/65) and (925007/65).
- 4. Insulation resistance apparatus (MEGGAR) Serial No.: (32772-2).

■ Test Sample:

- Test sample was chosen under the responsibility of the client.

Tests:

- 1- Marking.
- 2- Insulation Resistance.
- 3- Electric Strength.
- 4- Total Input Power.
 - 4.1 LED luminaire Power.
 - 4.2 Displacement Factor.
- 5- Luminous Flux.
- 6- Correlated Colour Temperature (CCT).
- 7- Colour Rendering Index (CRI).
- 8- Luminaire Efficacy.







الشركة القابضة لكهرباء مصر قطاع المعامل والبحوث والاختبارات مركز أبحاث الجهد الفائق الكبلا٢٥ طربق الفامرة /لاسكندرية المبعراوى رقم التقرير: (٢٥٤/ ٢٥٤)

Test Method and Results:

1- Marking

Testing Date: 1/6/2022

Testing Engineer: Mohamed Antar

- The test was carried out according to clause (3.4) of IEC (60598-1).
- The marking shall be legible, marking labels shall not be easily removable and they shall show no curling.
- The LED luminaire met the requirements.

2- Insulation Resistance

Testing Date: 1/6/2022

Testing Engineer: Mohamed Antar

- The test was carried out according to sub-clause (10.2.1) of IEC (60598-1).
- The insulation resistance shall be more than (2) $M\Omega$.
- The measured value of the insulation resistance was (15.8) $G\Omega$.
- The LED luminaire passed the test

3- Electric Strength

Testing Date: 1/6/2022

Testing Engineer: Mohamed Antar

- The test was carried out according to sub-clause (10.2.2) of IEC (60598-1).
- No flashover or breakdown shall occur during the test.
- The LED luminaire passed the test.

4- Total Input Power

Testing Date: 6/6/2022

Testing Engineer: Mohamed Khairy

- The test was carried out according to clause (7) of IEC (62722-2-1) as following:

4.1 LED luminaire Power

- The test was carried out according to clause (7.1) of IEC (62717).
- The initial power consumed shall not exceed the rated power (100) Watt by more than (10)%.
- The measured value of the total power at the rated voltage (220 V) for the LED Luminaire was (102.09) Watt.
- The LED luminaire met the requirements

4.2 Displacement Factor

- The test was carried out according to clause (7.2) of IEC (62717).
- The displacement factor shall not be less than (0.99) by more than (0.05).
- The measured value of Total Harmonic Distortion (THD) for current was (7.26) %.

Mikhaim





الشركة القابضة لكهرباء مصر قطاع المعامل والبحوث والاختبارات مركز أبحاث الجهد الفائق الكيو٧٧ طريق القامرة الامكندرية الصعراوي رقم التقرير: (٢٠٢٧/ ٢٥٤)

- The harmonic currents shall not exceed the relative limits given in [Table 2] of IEC (61000-3-2).
- The maximum permissible harmonic current expressed as a percentage of the input current at the fundamental frequency illustrated in the following table:

No.	Harmonic order	Maximum permissible	Measured value	Remark
1	2	2	0.33	Pass
2	3	28.95	4.79	Pass
3	5	10	2.8	Pass
4	7	7	1.3	Pass
5	9	5	2.005	Pass
6	$11 \le n \le 39$ (Odd harmonic only)	3	0.75 (Max.)	Pass

- The measured value of the power factor was (0.965).
- The displacement factor value for the LED Luminaire was (0.967).
- The LED luminaire met the requirements

5- Luminous flux

Testing Date: 6/6/2022

Witness Engineer: Mohamed Khairy

- The test was carried out according to clause (8.1) of IEC (62722-2-1).
- The initial luminous flux shall not be less than the rated luminous flux (12000) lm, by more than (10) %.
- The measured value of the luminous flux for the LED Luminaire was (12347.8) lm.
- The LED luminaire met the requirements

6- Correlated Colour Temperature (CCT)

Testing Date: 6/6/2022

Witness Engineer: Mohamed khairy

- The test was carried out according to clause (9.2) of IEC (62722-2-1).
- The measured value of correlated colour temperature (CCT) for the LED Luminaire was (5877) K.
- The LED luminaire achieved the above value.

7-Colour Rendering Index (CRI)

Testing Date: 6/6/2022

Witness Engineer: Mohamed khairy

- The test was carried out according to clause (9.3) of IEC (62722-2-1).
- The measured value of initial Colour Rendering Index (CR1) for the LED Luminaire was (82.1).
- The LED luminaire achieved the above value.

M. Khain





الشركة القابضة لكهرباء مصر قطاع المعامل والبحوث والاختبارات مركز أبحاث الجهد الفائق

الكيلو٢٧ طريق القاهرة /الاسكندرية الصحراوي رقم التقرير: (٢٠٢/ ٢٥٤)

8-Luminaire Efficacy

Testing Date: 6/6/2022

Witness Engineer: Mohamed Antar

- The test was carried out according to clause (8.3) of IEC (62722-2-1).
- The LED Luminaire efficacy shall not be less than (90) % of the rated LED Luminaire efficacy (120) lm/W.
- The measured value of luminaire efficacy was (120.95) lm/W.
- The LED luminaire met the requirements

Conclusion:

- The LED street lighting luminaire (100) watt - Type: (TU) - Rated Input power: (100) Watt - Manufactured by TEBA for Development Industries - Made in Egypt, achieved the results of tests mentioned in this report according to IEC. The customer to check of carrying out other remaining tests specified in IEC standard and not included in this report.

Notes:

- Tests were carried out on the above specimen only without any responsibility concerning other untested
- The tests were carried out without any obligation on Egyptian Electricity Holding Company
- This test report shall not be reproduced except in full, without written approval of EHVRC.
- This report and results are related only to the tested specimen.
- This report to be stamped for use.
- This test report is forbidden to be reproduced without prior permission of the Extra High Voltage Research Centre.
- This report is valid for the tested specimen and for a maximum three years unless there is a change in the design or specifications mentioned in this report.

Test Engineers:

A.C. Lab.

Eng. Mohamed Antar

Imp. Lab.

N.Khai Eng. Mohamed Khairy

awzy Mahmoud

General

Sherif...




الشركة القابضة لكهرباء مصر قطاع المعامل والبحوث والاختبارات مركز أبحاث الجهد الفائق الكبو١٧ طربق الفامرة //٣٠كندرية الصعراوي رقم التقرير: (٢٥٤/ ٢٠٢/)




















Color Parameters:

Chromaticity Coordinates:x=0.3241 y=0.3416/u'=0.2010 v'=0.4766 duv=0.00408 Tc-5877K Dominant WL:Ld-503.8nm Purity-2.8%

Ratio:R-12.8% G-83.7% B-3.5% Peak WL:Lp-995.6nm HWL:0.3nm

Rendering Index:Ra=82.1 TM-30: Rf=74 Rg=94 CQS: TLCI = 51

R1 -70 R2 -75 R3 -79 R4 -74 R7 -79

R14-88 R9 --29 R11-75 R12 R8 -60 R10-42

E = 0.4096 lx Ee = 0.0016 W/m2

R5 -78

R15-64